BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92
E-TND-04/2009-10 Dated: 14.07.2009

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No. 29

Name of the Work :Improvements and Asphalting Roads and Drains at Coffee Board Layout Main Roads, in Ward No. 7- Byatarayanapura, Kodigehalli Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	99.00	KSRRB 300-1 : Earthwork excavation by manual means in **Ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. **(Page No. 126 & Item No. 19.1)**	Cum	56.16	
2	61.20	KSRB 2-1.1 : Earthwork in surface in Oridnary Soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines **and cables)** and removing the excavated stuff to a distance not exceeding 50 m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) /2.3.1 **(Page No. 5 & Item No. 2.1)**	Cum	108.00	
3	33.45	KSRRB M400-17 : Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the mtareial with water at OMC in mechanical mix plant carriage of mixed mehtod of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (Page No. 143 & 20.18)	Cum	1061.64	
4	14.85	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 7.5 cms thick. (Page No. 24 & 5.31)	Cum	305.42	
5	3706.50	KSRRB 500-2 : Cleaning the existing black topped **surface with brooms,** soft **brushes** and finally dusting with old gunny bags and / or compressed air to received bituminous treatment iincluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. **(Page No. 148 & Item No. 21.2).**	Sqm	2.27	
6	3706.50	KSRRB 500-7: providing and applying **primar coat** on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding clearing of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5, **No. 149/ Item No. 21.7/ PWD SR 2010-11**	Cum	24.62	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	92.66	KSRRB M500-18 : Providing and laying semi dense bituminous concrete 25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver. **(P - 151 & I - 21.20.5)**	Cum	7379.38	
8	160.20	Lead for disposal of debris shall be payable at Carriage rates by mechanical means with all lead and lift, loading, undloading and labour charges etc.,complete and as per the directions of the Engineer-in-charge of the work.	Qtl		

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟಿಂಡರ್ ಪರಿಶೀಲನೆಯನ್ನು
ವಿದ್ಯುಚ್ಛಕ್ತಿಯ ಸಂಖ್ಯೆ KA
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದಿಸಲಾಗಿದೆ.

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ ಯಲಹಂಕ ವಲಯ
ಬೆಂಗಳೂರು 560092